Bruhat Bangalore Mahanagara Palike
Excecutive Engineer Yelahanka Project Division
Name of Work: Improvements to crematoriums in ward No.07
Agency:-M/s KRIDL
Schedule - B

Sl No	Quantity	Description of Item	Unit	Approved Rates of M/s KRIDL	
				In Figures	In Words
1	3.60	KSRRB M200-12.1 Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled material, disposal of unservicea ble material and stacking the serviceable material with all lifts complete as per specifications. - LIME CEMENT CONCRETE by manual means (I. 18.18, P. 137)	Cum	403.92	Rupees Four Hundred Three And Paise Ninety Two Only
2	72.00	KSRB 5-14.1 : Providing and constructing load bearing wall with solid concrete blocks of size 400x200x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 with all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work.(Pg No.25, Item No.5.27.1)	Cum	1011.96	Rupees One Thousand Eleven And Paise Ninety Six Only
3	3.60	KSRB4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20 mm and down size graded granite matel coarse aggregates @ 0.69 cum and fine aggragtes @ 0.459cum, machine mixed concrete laid in layers not eceeding 15 cms, thick well compacted, in foundation, plinth and cills including cost of all materials, labour HOM machinery curing complate as per specifications. (Page No. 12. Item No. 4.6)	Cum	5876.28	Rupees Five Thousand Eight Hundred Seventy Six And Paise Twenty Eight Only
4	32.40	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineerin - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete) Page No. 262 / Item No. 37.2, PWD SR 2016-17	Tonne	884.52	Rupees Eight Hundred Eighty Four And Paise Fifty Two Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	uantity	Description of Item	Unit	Approved Rates of M/s KRIDL	
				In Figures	In Words
5	360.00	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint. Page No. 262 / Item No. 37.4, PWD SR 2016-17	Sqm	349.92	Rupees Three Hundred Forty Nine And Paise Ninety Two Only
6	162.00	Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint Page No. 262 / Item No. 37.3, PWD SR 2016-17	Sqm	711.72	Rupees Seven Hundred Eleven And Paise Seventy Two Only
7	0.04	KSRB 9.4-2 : Providing Honne wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making laster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications. (PWDSR 2015-16, P. 51, I. 9.11)	Cum	111083.40	Rupees One Lakh(s) Eleven Thousand Eighty Three And Paise Forty Only
8	1.58	Providing and fixing in position fully panelled Honne wood shutters for doors, styles and rails of 30mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications. (excluding cost of fixtures) (PWDSR 2015-16, P. 52, I. 9.21)	Sqm	4472.28	Rupees Four Thousand Four Hundred Seventy Two And Paise Twenty Eight Only
9	1.58	KSRB15-17 : Painting of wood surface KSRB 15-17.1 : Applying priming coat over new wood surface and / or wood based surface with white lead paint priming including preparing the surface after throughly cleaning oil, grease, dirt and foreign matter, sand papering and knotting ready mix paint including cost of materials, labour, complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work. (PWDSR 2015-16, P-No: 118, Item No: 15.55)	Sqm	35.64	Rupees Thirty Five And Paise Sixty Four Only
10	684.07	KSRB 24-1 : Removing white wash or colour wash by steel brushing and / or scraping, sand papering and preparing wall surface smooth including repairs to scraches, cost of labour, complete as per specifications. Specification No.KBS. (P.No. 128/ I.No. 16.1.1 of CSR 2016-17)	Sqm	6.48	Rupees Six And Paise Forty Eight Only

Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Description of Item	Unit	Approved Rates of M/s KRIDL	
				In Figures	In Words
11	684.07	KSRB 15-14.1 : Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after thoroughly brooming the surface free from mortar drops and other foregin matter including preparing the surface even and sand paper smooth, cost of materials, labours, complete as per specifications PWD SR 2015-16 (P.116 /I. 15.49.1)	Sqm	76.68	Rupees Seventy Six And Paise Sixty Eight Only
12	109.20	"Supplying and fixing pressed steel window frame of size 100 x 50mm manufactured from 1.25 mm thick carbon steel or imported steel strips with neat mitred joints at 900degree for window openings and shall be suitable to fix M.S. grills as per design and drawings using 12mm dia rods at 100mm Centre to Centre horizontally and two members of M.S flats of 6mmx40mm size at 150mm apart, welded into a frame of 6mmx40mm size M.S. flats with 16mm size lugs, and 8 Nos. of 100mm size hinges, 4 Nos of Butt Stay pins and 4 Nos. Tower bolts and shutters half panelled and hallf glazed with shutters made out of seasoned honne wood, styles of 30mm thick and 100mm width and rails of 30mm thick and 100mm width and using 4mm thick pin headed glass and panel, filling with 12mm thick particle board of exterior grade bonded with phenol formal dehide resin and the shutter shall be rot proof vermin proof, heat resistant guaranteed against shrinkage, warp age and such other defects for a period of 3 years.This shall be as per approved drawing, specification and direction including cost of conveyance, manufacturing painting with 2 coats enamel paint over one coat of primer, cost of labour for	Sqm	4104.00	Rupees Four Thousand One Hundred Four Only
13	10.13	KSRRB 300 - Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 (p 142 i 19.1)	Cum	88.56	Rupees Eighty Eight And Paise Fifty Six Only
14	50.00	Providing and laying reinforced cement concrete pipe NP2 for culverts including pointing ends, and fixing collars with cement mortar 1:2 including cost of all materials, labour, curing complete as per specifications. Specifications. No. KSRB 1000, 2300 MOST Specification No.1000 / 2300 - - 250mm dia (P 253 I 34.7.2)	Mtr	596.16	Rupees Five Hundred Ninety Six And Paise Sixteen Only
15	288.00	KSRB 15.3.13 : Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Page No. 114 / Item No. 15.21	Sqm	208.44	Rupees Two Hundred Eight And Paise Forty Four Only

Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Description of Item	Unit	Approved Rates of M/s KRIDL	
				In Figures	In Words
16	288.00	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications.	Sqm	74.52	Rupees Seventy Four And Paise Fifty Two Only
17	6.00	Supplying capacitor type ceiling fan complete with down rod blades, shackle, canopies etc, for operation on 230 volts, and 50 cycles. Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system and as per technical data approved	Nos	2376.00	Rupees Two Thousand Three Hundred Seventy Six Only
18	6.00	Fixing a ceiling/wall mounting fan of all capacities and all types to the existing S hook with fan regulator to the existing board together with supplying and fixing a 5 ampers ceiling rose, necessary length of 23/0.0076 inch pvc insulated twin twisted cooper wire and wiring completely.	Nos	2534.00	Rupees Two Thousand Five Hundred Thirty Four Only
19	2.00	Solar water heating system-500 liters per day capacity @60 degree celsius -FPC type solar water heater	Nos	98076.00	Rupees Ninety Eight Thousand Seventy Six Only
20	15.00	Providing and fixing ornamental benches (delhi benches) as per design drawings specifications and direction of engineer incharge	Nos	8500.00	Rupees Eight Thousand Five Hundred Only
21	3.00	Geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the Hand pump, MWS of P.W.S.S by vertical electrical sounding by adopting Venner or Schlumberger's method, including reconnaissance survey of geological formation, Geophysical investigation of existing Ground Water in the vicinity, its quality, quantity and acceptability of the users indicating the location of site, recommended depth of casing pipe required an extra depth of 1.0 meter in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site., engaging techinical personal and labour required etc., as per Specification and direction (P.47, I. 9.4) PRED.SR 2012-13	Each BW	1938.46	Rupees One Thousand Nine Hundred Thirty Eight And Paise Forty Six Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Description of Item	Unit	Approved Rates of M/s KRID	
				In Figures	In Words
22	150.00	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.,) P. 46 / It. 9.1 PRED SR 2012-13 0 to 50 m	RMtr	315.18	Rupees Three Hundr Fifteen And Paise Eigh Only
23	150.00	50 to 100 m	RMtr	412.00	Rupees Four Hundred Twelve Only
24	150.00	100 to 150 m	RMtr	458.35	Rupees Four Hundred Fi Eight And Paise Thirty Fi Only
25	150.00	150 to 200 m	RMtr	484.10	Rupees Four Hundred Eighty Four And Paise Te Only
26	150.00	200 to 250 m	RMtr	560.32	Rupees Five Hundred Sixt And Paise Thirty Two Onl
27	150.00	250 to 300 m	RMtr	600.49	Rupees Six Hundred And Paise Forty Nine Only
28	150.00	Supply of ISI mark 175 mm nominal bore, plain end steel casing pipe grade of steel fee 410 of wall thickness 5.4mm thick confirming to IS 4270:2001 and latest amendments, electric resistance welded steel tube material and confirming to IS 1387/1993 and manufactured by basic open hearth electric or basic oxygen process in random length of 5 to 7 mts. Both ends threaded confirming to IS 4270:2001 and the other end with screwed pipes. All pipes shall be reasonably free from defects. The tubes shall be reasonably straight should be with ISI marking, weighing 25.10 Kg/mtr.(Inclusive of all taxes and durties). Prices include collar-medium duty.(Piii, It, 84)	RMtr	1364.75	Rupees One Thousand Three Hundred Sixty Four And Paise Seventy Five Only
29	120.00	Providing 200mm dia PVC Pipe10kg/cm2 SE PRED PAGE NO 15 IT 3.4.3 G	RMtr	1144.00	Rupees One Thousand One Hundred Forty Four Only
30	3.00	Providing and supllying 175mm dia M.S.Cap (as per PREC SR 2012-13) etc., complete as per specifications and direction of the Engineer--in-charge (Piii, It 85)	Nos	100.00	Rupees One Hundred Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Description of Item	Unit	Approved Rates of M/s KRIDL	
				In Figures	In Words
31	3.00	Supplying and delivery of sub mersible pumpset suitable for borewell of 165mm dia with specified duty conditions as detailed below and satisfied in BIS with ISI mark with a minimum efficeiency of 42% pump shall confirm to IS 8034/2002 and motor confirming to IS 9283/1995 with ISI certification with latest amendemnets for the following, Page No. XXXXII 17.5 HP 13kw 40 stage sub mersible pumpset	Nos	78036.00	Rupees Seventy Eight Thousand Thirty Six Only
32	870.00	Providing and fixing in galvanised mild steel tubes (Heavy class as per IS 1239 Part-1990) 50mm dia nominal bore with all fittings including cost of all materials labour charges HOM of euipment and testing complete as per specification (PWD SR 2015-16 P NO.87, It No.13.6)	Mtr	457.92	Rupees Four Hundred Fifty Seven And Paise Ninety Two Only
33	1860.00	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 Volts. P. No. 49/ I No. 29-c(1) 2.5 Sqm mm of 36 strands 0.3mm dia Group - A KPWD Electrical SR 2014-15	Nos	188.70	Rupees One Hundred Eighty Eight And Paise Seventy Only
34	3.00	Erection of pumpset including aligning and balancing with all necessary erection materials and labour including supply and erection of one pair supporting clamps, one borewell cap. Cable clips with bolts, nuts, valves guages etc., involoved in the job (Necessary GI pipe and specials with be supplied by the board at the site free of cost) (As per rate approved KUWS & DB for year 2008-09	Nos	3000.00	Rupees Three Thousand Only
35	159.00	Supply heavy duty galvanized mild steel color suitable for 50mm dia nominal bore galvanized mild steel	Nos	130.00	Rupees One Hundred Thirty Only
36	3.00	Supply of non return valve suitable for 50mm dia nominal bore galvanized mild steel tube (P No 95, It No.13.55)	Nos	1409.80	Rupees One Thousand Four Hundred Nine And Paise Eighty Only
37	3.00	Supplying of on load charges over switches 4 poles 415V, 5hr ac supply 100-125 amps group A (BWSSB SR Rate P No 3481, It Group A)	Nos	9845.00	Rupees Nine Thousand Eight Hundred Forty Five Only
38	3.00	Supply and fully automatic star delta uint push button type with suitable wires, 3 conatactor one adjustable thermal timer mounted on a common base late held in steel enclosure for use on 440/440 volts 3 phase and wired after to the existing wooden board for motor 12.5 HP (BWSSB SR P No. 335. It No.10(A)	Nos	5665.00	Rupees Five Thousand Six Hundred Sixty Five Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-94

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Description of Item	Unit	Approved Rates of M/s KRIDL	
				In Figures	In Words
39	3.00	Erection of single phase preventor ammeters/including fixing selctor switch/current operated earth leakage circuit breakers voltage operated circuit breaker above 100A fuse channel set (3 Nos) HRC fuses above 100A (3 Nos) including transportation charges from stores to spot (P-28. It No.16)	Nos	1500.00	Rupees One Thousand Five Hundred Only
40	3.00	Fabricating, supplying and mounting 1200x900x350 mm MS box of 18 SWG suitable for floor /wall mounting, fully weather proof with double stanted top as per drawing with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with approved colour enamelled metal paint etc., complete box of 36200 sqcm @ Rs.0.20 18 SWG (BWSSB SR P-352, It No 41)	Nos	7866.00	Rupees Seven Thousand Eight Hundred Sixty Six Only
41	3.00	Supplying and fixing miniature circuit breakers/solaters on existing MCB distribution boards using necessary fixing materials and wiring complete as requireds32 to 63 amps triple pole with all lead and lift, loading, unloading and labour charges etc complete as per specifications (BWSSB SR P-352, It No 15)	Nos	2090.00	Rupees Two Thousand Ninety Only
42	3.00	Supplying and running of GI copper strips or grounding connections using necessary fixing materials required 600x600x3mm GI plate (P-378, It 9(E)	Nos	1072.00	Rupees One Thousand Seventy Two Only
43	18.00	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete.... P No. 32/I No 3d KPWD Electrical SR 2010-11	Nos	201.40	Rupees Two Hundred One And Paise Forty Only
44	70200.00	Fabrication supplying and mounting MS box of 16 SWG suitable for floor /wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primer paint and finally finished with approved colour enamelled metal paint etc., complete box of 21600 sqcm @ Rs.0.33 P.No. 49, I. No. 6.40.2 KPWD Electrical SR 2014-15	Sqm	0.33	Rupees And Paise Thirty Three Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Description of Item	Unit	Approved Rates of M/s KRIDL	
				In Figures	In Words
45	3.00	Supplying and delivery at site brand new star / Essen/ Lotus/Sun-shines/Adarsh/ GK Controls best indigenous make combined energy meter - cum- control panel board unit of size 600x450 x200 mm minimum mechanically strong vermin and water proof. The unit shall have two detachable doors suitable for operation on 3 ph, 50Hz, 380/440 volts, A.C supply with spring loaded latch, locking device with a key ribs should be provided inside the door, canopy apron and louvers ventilators shall be provided. the combined energy meter cum- control panel board unit suitable for operation. The panel board shall be fabricated on single unit in the above components for suitable pumpset. PRED Bangalore Circle SE Approved Date 30.07.2010 15HP to 30 HP Star Delta Starter	Nos	10000.00	Rupees Ten Thousand Only
46	3.00	KSRB 13.6.3-6 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS 13.2.6/13.3 (P.81/I.13.37 PWD SR - 2015-16)	Nos	1843.34	Rupees One Thousand Eight Hundred Forty Three And Paise Thirty Four Only
47	90.00	Supplying of LTUG cable having aluminium condutor PVC insulated shethed, galvnised steel, wire / steel tap armoured cable with PVC outer sheathing 1.1 KV class.P No. 68/ I No. 4(d) 4 core 16 Sqmm KPWD Electrical SR 2010-11	RMtr	140.40	Rupees One Hundred Forty And Paise Forty Only
48	90.00	Labour charges for laying of 1.1 K.V class UG cable (PWD Electrical SR-1999-2000, P No. 69 / I No. Ia In existing trencg/duct 6Sqmm to 16 Sqmm) KPWD Electrical SR 2010-11	RMtr	10.80	Rupees Ten And Paise Eighty Only
49	75.00	Digging or trenching of 0.6m deep x 0.5 mtr wide refilling the trench to the required ground level and consolidating etc., complete (as per Civil SR KSRB 1-2 P-7) P No. 70/ I. No. 6-c KPWD Electrical SR 2010-11	RMtr	117.00	Rupees One Hundred Seventeen Only
50	12.00	Supplying and fixing of Class A (meaium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class P. No. 70/ I No.9-A KPWD Electrical SR 2010-11	RMtr	345.00	Rupees Three Hundred Forty Five Only
51	3.00	Supplying and fixing L.T. cast Iron pot head suitable for 1.1 KV class UG cable filled with necessary bituumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc., P. No. 70/ I No. 10-b KPWD Electrical SR 2010-11	Nos	280.00	Rupees Two Hundred Eighty Only
52	14.22	Cutting the road surface for pipeline trenches and disposing of the excavated stuff as directed including barricading danger lighting etc in following classifications Cutting in Cement concrete road surface (Page 269 Item 37.40)	Cm	727.16	Rupees Seven Hundred Twenty Seven And Paise Sixteen Only

Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Description of Item	Unit	Approved Rates of M/s KRIDL	
				In Figures	In Words
53	4.74	KSRB 2.6 : Providing and filling sand in foundation upto plinth to required depth for sub soil treatment including watering ramming with lead upto 50m. and lift upto 1.5m complete as per specifications.Specification No.KBS 2.10.2(Page No7., Item No. 2.13)	Cm	2183.60	Rupees Two Thousand One Hundred Eighty Three And Paise Sixty Only
54	10.68	KSRB 4 - 1.6 : Providing and laying in position plain cement concrete of mix M 15 with cement @ 240 kgs, with 20 mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation plinth and cills including cost of all materials, labour HOM of machinery curing complete as per specifications. Specification No.KBS 4.1, 4.2 (Page No.12, Item No. 4.6)	Cm	5747.32	Rupees Five Thousand Seven Hundred Forty Seven And Paise Thirty Two Only
55	3.00	Bescom deposits and other service charges	Nos	18000.00	Rupees Eighteen Thousand Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92